

December 6, 2019

Mr. William Wardell Project Manager Capital Projects Division Washoe County Reno, NV

Re: Northern Nevada Adult Mental Health Campus Our Place GMP 4 Site Work and Fencing 480 Galletti Way Sparks, NV

Dear Mr. Wardell,

Q&D Construction is pleased to provide the Guaranteed Maximum Price GMP 4 deliverable per our preconstruction services agreement for the Homeless Housing Project. The deliverable includes a comprehensive, detailed estimate for the project's anticipated construction program along with an associated estimating narrative, and the current project schedule.

The GMP 4 deliverable is based upon the following documents provided by Paul Cavin Architect LLC.

• Site Improvements Construction Documents dated 9/20/19

We are very appreciative of the opportunity to be a part of this project and look forward to collaborating with you on the successful delivery of the project.

If you have any questions at all about Q&D's GMP 4 Deliverable please do not hesitate to contact me.

Sincerely,

Q&D Construction

Neil Bartlett Senior Preconstruction Manager

Our Place GMP 4 Cost Summary

1)	Material, Labor, Sub & Equip	\$	801,397
2)	General Conditions	\$	183,065
3)	Builder's Risk Insurance (0.75%)	\$	8,396
4)	Liability Insurance	\$	10,133
5)	P&P Bond	\$	8,365
6)	Fee (5.0%)	\$	53,308
7)	SUBTOTAL	\$	1,064,664
8)	Owner Contingency Allowance	\$	0
0)	Guard Shack Allowance	¢	20 000
9)	Guaru Shack Allowance	\$	28,800
,	Contractor Contingency	э \$	28,800 <u>26,004</u>

Schedule:

• 4 Months of construction

Alternates:

• None

Allowances:

• Guard Shack \$28,800

SCOPE OF WORK

01 00 00 General Conditions

- 1. <u>Project Management Staff</u>: project manager ¼ time for 4 months, ¼ time project engineer 4 months, and project administrator supporting the project.
- 2. <u>Field superintendent</u> One (1) half time superintendent for 4 months on the project. Also, One (1) half time Labor Foreman Carpenter Foreman for 16 weeks of the project.
- 3. <u>Temporary utilities</u>: Temporary power distribution and temporary lighting; monthly electric energy cost is excluded; monthly water consumption cost is excluded; final months gas consumption cost to check permanent facilities is excluded; monthly temporary phone and data cost is included.
- 4. <u>Construction facilities</u>: project office will be housed in the existing building 2A; tool trailer; chemical toilet rental and cleaning; ice, cups, and drinking water; construction office supplies; jobsite cell phones monthly expense; demobilization of construction facilities and temporary construction, temporary computer networks and project management software.
- 5. <u>Temporary construction</u>: Construction fence rental; temporary fire protection, signage, safety equipment.
- 6. Temporary barricades and enclosures:
- 7. <u>Project cleaning</u>: continuous cleanup of the project site; dumpsters; cleaning of the adjacent street during construction activities; final cleaning.
- 8. Liability Insurance
- 9. Forklift and operator.

02 00 00 Existing Conditions and Sitework

- 1. Selective Demolition
- 2. Earthwork and Site Work

03 00 00 Concrete

- 1. Cast-in place concrete flatwork
- 2. Curbs, gutters, sidewalks

13 00 00 Special Construction

1. Allowance for Gate House

25 00 00 / 26 00 00 / 27 00 00 Electrical

1. Excavate and backfill conduit for electrical gates

Other Costs & Fees

- 1. Construction Contingency \$26,004
- 2. Contractor's Overhead & Fee 5.0%

SERVICE. INTEGRITY. QUALITY.

- 3. Builders Risk Insurance 0.75%
- 4. Performance & Payment Bond
- 5. Prevailing Wages

Exclusions

- 1. Architectural, civil, structural, and MEP designs.
- 2. Water rights.
- 3. Water tap, sewer tap, development fees or other utility fees.
- 4. Planning, Zoning, and Entitlement research & submittals.
- 5. §1704 Special Inspections.
- 6. Unsuitable soils haul-off or additional structural soil import
- 7. Electrical
- 8. Handrail(None Shown)

SERVICE. INTEGRITY. QUALITY. P.O. Box 10865, Reno, Nevada 89510 | Main Office: 775.786.2677 | Fax: 775.786.5136 www.qdconstruction.com | NCL: 8197 A & B