

- 
- ☐ SO. CALIFORNIA: 2044 South Vineyard Avenue, Ontario, CA 91761 • (909) 930-1822 • FAX (909) 923-2356
  - ☐ NO. CALIFORNIA: 800 East Grant Line Road, Tracy, CA 95376 • (209) 830-8600 • FAX (209) 830-8884

Date: 10/8/2020  
Quote Number: 100033

Washoe County Community Services  
1001 E. Ninth St. Bldg. A  
Reno, NV 89512

Sourcewell   
Contract # 122017-SCA

Attention- Dylan Menes

Reference- Sewer Equipment Company of America Eco 900 9yd Combination Truck

Dear Mr. Menes,

We are pleased to quote you One (1) Eco 900 9 Yard Combination Truck Mounted on a New Western Star 4700:

**Vacuum System:**

- 4400 CFM Blower
- 8" Vacuum Hose system
- 18" Hg vacuum rating
- Dual Cyclone Separator
- Dual Element 10 Micron Final Filter
- Remote Vacuum Relief
- Variable Volume Delivery
- Analog Vacuum Display
- (6) Tube / Tube Rack

**Boom:**

- Telescoping Boom System
- Telescoping Reach 17' 2" to 27' 2"
- Hydraulic Powered Boom
- 180° Working Radius
- Boom Joystick Control

**Debris Tank:**

- 9 Cubic Yard Capacity
- Hydraulic Dump, 50° Dump Angle
- Dual Ported Rear Door w/ Knife Valve
- Dump Height 60"
- Hydraulic Open/Close/Lock Door
- Debris Body Pump Off System (4" hydraulic driven pump rated @ 800 gpm located on rear door of debris box, includes swing out decant screen) ( Torque PTO Bolts & Studs @ 50ft-lbs) 90 Degree Mounting
- Modified Decant Screen
- Debris Body Wash Out System (includes dual nozzles in debris box)

- 
- SO. CALIFORNIA: 2044 South Vineyard Avenue, Ontario, CA 91761 • (909) 930-1822 • FAX (909) 923-2356
  - NO. CALIFORNIA: 800 East Grant Line Road, Tracy, CA 95376 • (209) 830-8600 • FAX (209) 830-8884

**Water System:**

- 1000 Gallon Capacity Water Tank
- Giant plunger style triplex
- 55 gpm @ 3000 PSI w/ 30 min run dry (includes drain valves)
- Black Duraprolene™ Water Tank Construction w/ 10 Year Warranty
- Cold Weather Recirculation System
- 2.5" Hydrant Fill system
- Air Purge Valve
- Variable Volume Delivery
- Low Water Warning Light
- Analog Pressure Display
- Front and Mid Ship Handgun Ports
- Additional 150 Gallon Duraprolene™ Water Tank W/ 10 Year Warranty - (between rails) Note: Subject to chassis load capacity specifications.
- Fill hose Storage Rack
- Standard Hydro excavation Cleaning Kit 20 GPM @ 2000 PSI ( 8" x 6' digging tube, 8gpm rotary digging wand, 10gpm linear nozzle (shipped loose), (2) 5' Extension wands and automatic reel w/ 75' of 3/8" hose)
- Central Washdown System (includes 50' of 1/2" hose on a spring retracting hose reel mounted mid-ship)
- Washdown Connection Driver Side with Loose 25' or 50' hose
- (2) Additional Extension Wands w/ High Flow Quick Connect

**Electrical:**

- NEMA 4 Control Panel
- Hour Meter (Blower & Water Pump)
- Military Spec. Sealed Switches
- Wireless Remote-Control Pendant (controls include hose reel payout/retrieve, water pump on/off, vacuum relief on/off, boom up/down, boom left/right, boom extend/retract and module kill switch)
- Enhanced Visibility Camera System (includes front and rear mounted camera heads with split screen monitor in cab)
- (6) LED Flush Mounted Strobes: (2) Front, (2) Side & (2) Rear Facing (factory standard)
- LED Arrow Stick (factory standard)
- LED Manhole Area Work Light
- LED Curbside Body Mounted Work Light
- LED Boom Mounted Work Lights (2) (complete with limb guard)
- LED Rear Mounted Work Lights (2) Located Above Rear Door
- LED Handheld Wireless 12v/110v Rechargeable LED Spotlight w/ Storage

**Truck:**

- Mounting to Approved Chassis
- Alum Toolbox 24"x42"x100" - Behind Cab
- Alum Toolbox 18"x18"x30" - Passenger
- Alum Toolbox 18"x18"x24" – Rear \*N/A ON SINGLE AXLE CHASSIS
- Alum Long Handle Storage
- LED D.O.T. Approved Lighting
- Air Purge Winterization System (supplied by chassis air system)
- Six (6) 28" D.O.T. Safety Cones And Holder
- Central Lubrication System

- 
- SO. CALIFORNIA: 2044 South Vineyard Avenue, Ontario, CA 91761 • (909) 930-1822 • FAX (909) 923-2356
  - NO. CALIFORNIA: 800 East Grant Line Road, Tracy, CA 95376 • (209) 830-8600 • FAX (209) 830-8884

## **Hose Reel & Hose:**

- Front Mounted Telescoping & Rotating
- 1000' x 3/4" Hose (Hose Reel Capacity 800' of 1" Hose)
- 25' Leader Hose in Lieu of Standard 10'
- Single Side Controls
- Automatic Level Wind With Hydraulic Up/Down Action
- Digital "Smart Counter" Footage Meter

## **Accessories:**

- (3) 8" x 6' Extension Tube
- (1) 8" X 4' Extension Tube
- (1) 8" x 6' Crowned Suction Nozzle
- (1) 6" x 10' Flat Discharge Hose
- BB Hose Guide
- Tri-Star (chisel point) nozzle
- DD (high flow) nozzle
- Finned Nozzle extension
- Nozzle Rack (Mounted midship toolbox)
- 25' Fill Hose
- Upstream Pulley Guide
- Washdown gun
- Cleaner, Tip, Torch, Small, w/Sewer
- (1) Hydrant Wrench
- (1) Paper Owner's Manual
- (1) Day Training Customer Location
- Training- Sewer Equipment University

## **Chassis:**

### **Western Star Conventional Chassis:**

- 2021 MODEL YEAR
- WHITE PAINT
- SET FORWARD AXLE - TRUCK
- DETROIT DD13 12.8L 450 HP @ 1625 RPM, 1900 GOV RPM, 1550 LB/FT @ 975 RPM
- JACOBS COMPRESSION BRAKE
- ALLISON 4000 RDS AUTOMATIC TRANSMISSION WITH PTO PROVISION

- 
- ☐ SO. CALIFORNIA: 2044 South Vineyard Avenue, Ontario, CA 91761 • (909) 930-1822 • FAX (909) 923-2356  
☐ NO. CALIFORNIA: 800 East Grant Line Road, Tracy, CA 95376 • (209) 830-8600 • FAX (209) 830-8884

## **Added Additional Options:**

- ADDITIONAL 200 GALLON DURAPROLENET™ WATER TANK W/ 10 YEAR WARRANTY- (driver side rail) Note #1: Subject to chassis load capacity specifications.
- 2" Y-STRAINER ON INLET FILL SYSTEM
- Special Paint Color for ECO 900

List Sales Price: \$322,773.00  
3% Sourcewell Discount: \$9,683.19  
Sales Price with Discount: \$313,089.81  
Western Star Chassis: \$123,220.00  
Total: \$436,309.81  
Freight, PDI, Training, Registration: \$10,000.00

**Sales Price Total: \$446,309.81**

**Options Not Included in Price: (If any options below are desired, please add to the price listed before the Sourcewell discount)**

- **DIGITAL WATER TANK LEVEL GAUGE** **\$939.00**
- **COLD WEATHER HYDROEXCAVATION CLEANING KIT 10 GPM @ 2000 PSI** **\$14,424.00**  
(includes 400,000 BTU diesel fired boiler in enclosed aluminum cabinet, 8' x 6' digging tube, 8gpm rotary digging wand, 10gpm linear nozzle (shipped loose), (2) 5' Extension wands and automatic reel w/ 75' of 3/8" hose) Note #1: Replaces the (2) standard 18"x18"x30" aluminum toolboxes on passenger side.
- **ADDITIONAL 18"x18"x30" ALUMINUM TOOLBOX** **\$967.00**  
(2 maximum mounted passenger side rail)

- 
- ☐ SO. CALIFORNIA: 2044 South Vineyard Avenue, Ontario, CA 91761 • (909) 930-1822 • FAX (909) 923-2356
  - ☐ NO. CALIFORNIA: 800 East Grant Line Road, Tracy, CA 95376 • (209) 830-8600 • FAX (209) 830-8884

**Special Notes:**

- 1. Delivery will be made via Drive Away from Dixon, Illinois to Tracy, CA. After Dealer PDI the unit will be driven to Washoe County.**
- 2. Estimated build completion date is March 2021. This date is subject to change with chassis delivery times.**
- 3. All prices are subject to all applicable taxes.**

The above price(s) are valid for 30 days.

Thank you for the opportunity to quote on your equipment needs. Should you have any further questions, please feel free to contact me.

Sincerely,

NIXON-EGLI EQUIPMENT CO.

*Dennis Schulgen*